



INDIRA GANDHI NATIONAL OPEN UNIVERSITY
CONSTRUCTION AND MAINTENANCE DIVISION
MAIDAN GARHI, NEW DELHI-110068
RE-INVITING QUOTATION

No. IG/CMD/EE(C)/NIQ/2019-20/188

Dated: 29.04.2019

The Executive Engineer (C) Construction & Maintenance Division re-invite on behalf of Vice-Chancellor, Indira Gandhi National Open University, sealed item rate quotations for the following work from the registered contractors of CPWD/MES/BRO/MCD/PWD/DDA or any other Govt./Autonomous body who have already executed at least one similar work costing 80% or two similar works costing 60% each or three similar works costing 40% each of estimated cost during the last seven years for any Govt. department. The quotations will be issued only on production of Original GSTIN No. and PAN No. proof for satisfactory completion of similar work duly certified by the competent authority of the client department.

S. No.	Name of work	Estimated cost	Earnest money	Last date of Issue of quotation	Date of submission and opening of quotation	Time allowed
1.	Repairs of roofs in warehouse No.-2, 3, 4 and plaster work in MPDD Store-I at IGNOU Campus.	₹ 1,34,527/-	₹ 3,363/-	10.05.2019	13.05.2019	01 Month (30 Days)

Quotation forms and conditions can be obtained from the office of the undersigned Indira Gandhi National Open University, Construction & Maintenance Division, Maidan Garhi on any working day up-to 02:30 PM on the date given above. The time for submission of quotations are up-to 03:00 PM which shall be opened on the same day at 03:30 PM on the date given above. The undersigned reserves the right to accept or reject any quotations without assigning any reason.

(Sanjay Kr. Bansal)

Name of work:- Repairs of roofs in warehouse No.-2, 3, 4 and plaster work in MPDD Store-I at IGNOU Campus.

SPECIFICATION & SPECIAL CONDITIONS OF CONTRACT:

1. Unless otherwise specified the work shall be carried out in accordance with the printed CPWD specification 2009 for the works at Delhi correction slips issued till the date of opening of tenders/quotation. In the event of any dispute the followings shall be the order of priority to decide the issue:-
 - a. Nomenclature of item read with special conditions of the contract and general specifications
 - b. CPWD specifications
 - c. ISI specifications
 - d. Instructions of Engineer In charge.
2. Before quoting the contractor shall inspect the site of work and shall fully acquaint himself about the conditions with regard to accessibility of site required for the satisfactory execution of work. No claim whatsoever shall be entertained by the department on this account.
3. The quantities shown in the schedule are tentative and may change as per site conditions. The Contractor shall not claim anything extra on this account. The payment shall be made as per actual quantities of work done and as per the conditions of the contract.
4. The work executed under the contract shall be subject to inspection carried out by the departmental officers. Any defects regarding workmanship or quality of material to be used as pointed out during or after completion of work by the departmental officers shall have to be rectified by the contractor and in case the contractor fails to do so, it will be got rectified by the department at the risk and cost of the Contractor.
5. All precautionary measures should be adopted for the safety purposes for any accident during the execution of work occurring at site, the contractor shall be overall responsible for the same.
6. Water if available shall be supplied to the contractor and 1% on account of water charges shall be recovered from him on the gross amount of work done. However, if the electricity is required for the work, the same shall be provided to the contractor and 0.25% on account of electricity charges shall be recovered from him on the gross amount of work done.
7. After the award of work, if the agency fails to start the work the earnest money and performance guarantee submitted by them will be 100% forfeited and the agency will be debarred for a period of three years to quote tender/quotation for IGNOU works.

Executive Engineer (C)

SCHEDULE OF QUANTITY

Estimated cost :- 1,34,527/-

Earnest Money :- 3,363/- (P.O. in favour of IGNOU)

Time allow :- 01 Month (30 days)

Issued to:-

Date of opening:-

Name of work:- Repairs of roofs in warehouse No.-2, 3, 4 and plaster work in MPDD Store-I at IGNOU Campus.

S. No.	Description	Qty.	Unit	Rate	Amount
1.	Raking out joints in lime or cement mortar and preparing the surface for re-pointing or re-plastering, including disposal of rubbish to the dumping ground, all complete as per direction of Engineer-in-Charge.	106	Sqm		
2.	Flush pointing with cement mortar 1:3 (1 cement : 3 fine sand) mixed with 2% of integral water proofing compound by weight of cement for flat tile bricks on top of mud phaska : With F.P.S. brick tiles	106	Sqm		
3.	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	0.34	Cum		
4.	Providing gola 75x75 mm in cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 stone aggregate 10 mm and down gauge), including finishing with cement mortar 1:3 (1 cement : 3 fine sand) as per standard design : In 75x75 mm deep chase	34	Mtr.		
5.	Providing high impact Polypropylene reinforced cement 6 mm thick corrugated sheets (as per IS: 14871) roofing up to any pitch and fixing with polymer coated J, or L hooks, bolts and nuts 8 mm dia. G.I. plain and bitumen washers or with self drilling fastener and EPDM washers etc. complete (excluding the cost of purlins, rafters and trusses), including cutting sheets to size and shape wherever required.	30	Sqm.		
6.	Providing & fixing UV stabilised fiberglass reinforced plastic sheet roofing up to any pitch, including fixing with polymer coated 'J' or 'L' hooks, bolts & nuts 8mm dia. G.I plain/bitumen washers complete but excluding the cost of purlins, rafters, trusses etc. The sheets shall be manufactured out of 2400 TEX panel rovigs incorporating minimum 0.3% ultra-violet stabiliser in resin system under approximately 2400 psi and hot cured. They shall be of uniform pigmentation and thickness without air pockets and shall conform to IS 10192 and IS 12866. The sheets shall be opaque or translucent, clear or pigmented, textured or smooth as specified. 2 mm thick corrugated (2.5" or 4.2" or 6") or step-down (2" or 3" or 6") as specified	72	Sqm.		
7.	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	170	Sqm.		
8.	15 mm cement plaster on rough side of single or half brick wall of mix: 1:6 (1 cement: 6 coarse sand)	170	Sqm.		

Executive Engineer (C)